


Senate Bill 3 Environmental Flows Science Advisory  
Committee (SAC)  
February 4, 2009


# MORE ON SEDIMENT TRANSPORT

# Effective discharge

- The flow responsible for the cumulative majority of sediment transport over time
- Maximum of the product of flow frequency and the sediment-transport rate
- Commonly assumed to have a recurrence interval of 1 to 2 years (Wolman and Miller, 1960); further assumption of bankfull




From Wolman and Miller (1960)




From Andrews (1980); scanned from Knighton (1998)

# Flow-duration curve




# Suspended-sediment load / discharge rating curve



- Plug in 'representative discharge' for each point on the flow-duration curve into the power relation of the sediment-Q rating curve

# Suspended-sediment histogram

- Put it in the histogram and determine effective discharge
- All of this is adequately explained in Biedenharn and others (2000)



# Decision points

- ⦿ Period-of-record
- ⦿ Sediment data
- ⦿ Discharge class intervals (more at the high end increases accuracy)
- ⦿ Other decisions regarding implementation

# Bedload effective discharge

- ⦿ Requires application of a bedload model
  - Bagnold (1977) excess stream power for sand bed
$$I_b = (\omega - \omega_c)^{3/2} (d/D_{50})^{-2/3}$$

- Gomez (2006) for gravel bed
$$I_b = [\omega(0.0115 D_{50}^{-0.51})]/0.63$$

$\omega$  is stream power per unit area (W/m<sup>2</sup>)

$\omega_c$  is critical stream power (W/m<sup>2</sup>)


$D_{50}$  is median bed-material size (mm)

$d$  is flow depth (m)

- ⦿ Requires additional data
  - Representative channel cross section
  - Bed-material particle size
  - Channel slope

# Additional data


- ⦿ We dangerously assume steady-state equilibrium



- ⦿ Channel slope: 0.00012
- ⦿ Median bed-material size: 0.009in
- ⦿ From National Cooperative Highway Research Program (2004)



# Bedload histogram



- Problem occurred because of original cross-section data; USGS stage-Q relations here showed a large cross-sectional area for very low flows (pond-like conditions)
- Hydraulic models, however, used that large cross-sectional area with the given slope to compute an unrealistic flow velocity

# References

Andrews, E.D., 1980, Effective and bankfull discharges of streams in the Yampa River Basin, Colorado and Wyoming: *Journal of Hydrology*, v. 46, p. 311–330.

Bagnold, R.A., 1977, Bed load transport by natural rivers: *Water Resources Research*, v. 13, p. 303–312.

Biedenharn, D.S., Copeland, R.R., Thorne, C.R., Soar, P.J., Hey, R.D., and Watson, C.C., 2000, Effective discharge calculation—A practical guide: United States Army Corps of Engineers ERDC/CHL TR-00-15, 63 p.

Gomez, B., 2006, The potential rate of bed-load transport: *Proceedings of the National Academy of Sciences*, v. 103, p. 17,170–17,173.

Knighton, D., 1998, *Fluvial forms and processes—A new perspective*: London, Arnold, 383 p.  
National Cooperative Highway Research Program, 2004, *Archived river meander bend database*: Washington, D.C., Transportation Research Board of the National Academies, 4 CD-set.

Wolman, M.G., and Miller, J.P., 1960, Magnitude and frequency of forces in geomorphic processes: *Journal of Geology*, v. 68, p. 54–74.